MOONEY AIRCRAFT, INC.

Service Bulletin



NUMBER: M20-148

DATE: 5-10-67

(This Service Bulletin is FAA D.O. Authorization SW-1 Approved)

SUBJECT:

Installation of Rudder Seals.

MODELS AFFECTED:

A/C M20F S/N's 670001 thru 670362.

TIME OF COMPLIANCE:

Within next 100 hours of operation.

INTRODUCTION:

Two (2) seals are to be added to the lower (bulb portion) rudder assembly to reduce the possibility of foreign matter accumulating inside this assembly.

INSTRUCTIONS:

Remove 460023 - Basic Rudder Assembly.

- I. Install 460040 Basic Seal as follows:
 - 1. Remove one (1) AN470-AD3 rivet-joining laps of 460023 7 and 9 'bulb' skin. (Reference Sketch).
 - 2. Insert seal-flanged upwards; locate approximately seven (7) inches from bottom edge of the rudder assembly.
 - Edge of seal to be flush with edge of 'bulb' skins.
 - 3. Attach this seal to 'bulb' skins with AN426-AD3 rivets—one (1) each through available pilot holes on seal.
 - 4. Install AN470-AD3 rivet (removed on item 1) 'picking-up' flange of seal.
- II. Install 460041 Basic Seal as follows:
 - 1. Insert seal-flanged down; locate approximately twelve (12) inches from bottom edge of rudder. Edge of seal and 'bulb' skins to be flush. (Reference Sketch).
 - 2. Attach forward flange—this skin to 'bulb' skins with AN470-AD3 rivets one (1) each through available pilot holes on seal.
 - 3. Attach aft flange—this seal to 460033 Basic Rib with AN470-AD3 rivets* one (1) each through available pilot holes on seal.
 - * May use CR 2249-4 Cherry Blind Rivets.

Re-install 460023 - Basic Rudder Assembly, and Rig according to 20 Series Mooney Service Manual.

PARTS LIST

- 1. 460040 Basic Seal
- 2. 460041 Basic Seal
- 3. AN426-AD3 Rivets
- 4. AN470-AD3 Rivets

These parts may be ordered from your local Mooney Distributor. Direct factory orders will not be accepted.




Figure 1